

# Appendix

## Reference material for evaluation of alternatives

# Research on Advance Bridge Construction in Puerto Rico

Puerto Rico Transportation Technology Transfer Center  
University of Puerto Rico, Mayagüez Campus



Puerto Rico  
Transportation Technology  
Transfer Center



# ABC (Accelerated Bridge Construction)

- ABC consists of construction methods that result in an overall decrease in construction time when compared to the conventional construction methods used to build bridges.
- It uses innovative planning, design, materials, and construction methods in a safe and cost-effective manner to reduce the onsite construction time that occurs when building new bridges or replacing and rehabilitating existing bridges.

# Superstructure Elements



Options that are compatible with ABC to be evaluated:

- **Alternative 1:** Full-depth Precast Deck Panels
- **Alternative 2:** Steel girders with integrated concrete deck
- **Alternative 3:** AASHTO beams with integrated concrete deck
- **Alternative 4:** Precast Decked Girders
- **Alternative 5:** Segmental Bridges

# Superstructure

## Alt. 1: Full-Depth Precast Deck Panels

- Description: The full-depth deck system is precast and subsequently installed.



# Superstructure



## Alt. 1: Full-Depth Precast Deck Panels



Installation of Precast Deck Panels

# Superstructure

## Alt. 1: Full-Depth Precast Deck Panels



## Superstructure



### Alt. 2: Steel girder with integrated concrete deck

- Description: A precast deck is cast over steel beams to form a pre-topped module. After the modules have been installed, deck edges are connected with closure pours.



# Superstructure

## Alt. 2: Steel girder with integrated concrete deck



## Superstructure

### Alt. 3: AASHTO beams with integrated concrete deck

- Description: A precast deck is cast over AASHTO concrete I-girders to form a pre-topped module. After the modules have been installed, deck edges are connected with closure pours.




# Superstructure

## Alt. 3: AASHTO beams with integrated concrete deck



# Superstructure

## Alt. 3: AASHTO beams with integrated concrete deck




# Superstructure

## Alt. 4: Precast Decked Girders


Description: Decked precast sections that are placed adjacent to one another to form the riding surface of the bridge.

It includes sections such as:

- Adjacent Box Beams
- Deck Bulb Tee Beams
- Double Tee Beams
- Box Girders
- NEXT Beam




**Adjacent Box Beams**



# Superstructure

## Alt. 4: Precast Decked Girders


**Double Tee Beams**



**AASHTO-PCI Box Girders**



**NEXT Beam**



# Superstructure


## Alt. 4: Precast Decked Girders

### Common Span Ranges for typical Precast Decked Girders

Precast/Prestressed Concrete Institute Northeast Covering New England and New York



#### PCI Northeast Bridge Beam Sections Common Span Ranges




# Superstructure

## Alt. 4: Precast Decked Girders

The Northeast Extreme Tee Beam (NEXT Beam) is a new section of precast decked girders.

- Depth 24" – 36" in 4" increments
- Typical Span Range 50 – 85'
- Width will vary 8'-0" – 12'-0"



# Superstructure


## Alt. 5: Segmental Bridges

- Description: Segmental construction involves the connection of numerous full-width concrete elements using post-tensioning. This is considered an ABC method when precast segments that are lifted into place and post-tensioned together are used.



# Superstructure Alternatives

Alt. 1: Full Depth Precast Deck Panels




Alt. 2: Steel girder with integrated concrete deck



Alt. 3: AASHTO beams with integrated concrete deck



Alt. 4: Precast Decked Girders



Alt. 5: Segmental Bridges



Substructure elements:

# Supports


Options compatible with ABC that will be evaluated:

- **Alternative 1:** Full Precast cap beam and columns connected at the top and bottom using grouted splice couplers
- **Alternative 2:** Full Precast cap beam and columns connected using post-tensioned ducts at the top and bottom
- **Alternative 3:** Full Precast cap beam with segmental columns connected using mechanical couplers and corrugated ducts
- **Alternative 4:** Full Precast cap beam and columns connected with corrugated duct at the tops and corrugated end placed into CIP footings

# Supports

Alt. 1: Full Precast cap beam and columns connected at the top and bottom using grouted splice couplers


- Columns and pier cap are precast elements.
- Connection between precast elements are made using grouted splice couplers.



## Supports


Alt. 1: Full Precast cap beam and columns connected at the top and bottom using grouted splice couplers

- Grouted Splice Couplers
  - Couplers are embedded in one element and they receive bar extensions from the adjacent element.
  - The coupler is grouted with high strength grout.
  - Emulates a reinforcing steel lap splice.



# Supports

Alt. 1: Full Precast cap beam and columns connected at the top and bottom using grouted splice couplers





Completed Pier

## Supports

### Alt. 2: Full Precast cap beam and columns connected using post-tensioned ducts at the top and bottom



- Similar to grouted couplers, except the coupler is replaced with a post-tensioning duct that is cast into one of the elements.
- These connections require longer dowel bar lengths than grouted couplers; however they can be less expensive and allow larger casting tolerances on the dowel bars.



## Supports


Alt. 2: Full Precast cap beam and columns connected using post-tensioned ducts at the top and bottom

For column to cap connection, use details from NCHRP Report 681



# Supports

Alt. 2: Full Precast cap beam and columns connected using post-tensioned ducts at the top and bottom



Completed Pier

## Supports


Alt. 3: Full Precast cap beam with segmental columns connected using mechanical couplers and corrugated ducts

- The columns are fabricated in segments and connected on-site.
- Ideal for projects where columns are large enough that cannot be transported or lifted as a single piece.



# Supports

## Alt. 3: Full Precast cap beam with segmental columns connected using mechanical couplers and corrugated ducts



## Supports

Alt. 3: Full Precast cap beam with segmental columns connected using mechanical couplers and corrugated ducts



## Supports

Alt. 4: Full Precast cap beam and columns connected with corrugated duct at the top and corrugated end placed into CIP footings

- It consists of a precast concrete column placed into cast-in-place concrete spread footings.
- It is made by placing the precast concrete column in the excavation, placing the footing steel, then casting the footing concrete.



## Supports

Alt. 4: Full Precast cap beam and columns connected with corrugated duct at the top and corrugated end placed into CIP footings



## Supports


Alt. 4: Full Precast cap beam and columns connected with corrugated duct at the top and corrugated end placed into CIP footings




**Footing Connection: Construction**

# Substructure: Supports Alternatives


Alt. 1: Full Precast cap beam and columns connected at the top and bottom using grouted splice couplers




Alt. 2: Full Precast cap beam and columns connected using post-tensioned ducts at the top and bottom



Alt. 3: Full Precast cap beam with segmental columns connected using mechanical couplers and corrugated ducts



Alt. 4: Full Precast cap beam and columns connected with corrugated duct at the tops and corrugated end placed into CIP footings



Substructure elements:

# Abutments



Options compatible with ABC that will be evaluated:

- **Alternative 1:** Precast Cantilever Abutments
- **Alternative 2:** Precast Integral or Semi-Integral Abutments
- **Alternative 3:** Geosynthetic Reinforced Soil (GRS) System

# Abutments

## Alt. 1: Precast Cantilever Abutment

- Cantilever- Girder and Abutment Wall not connected
  - Footing to wall stems connected using grouted splice couplers
  - Corrugated steel pipes in the abutment walls to reduce weight
  - Abutment cap is connected to the wall stems using a reinforced bar cage cast into the corrugated voids



# Abutments



## Alt. 1: Precast Cantilever Abutment



# Abutments

## Alt. 2: Precast Integral or Semi Integral Abutment


- Girder and Abutment Wall made continuous
  - Corrugated steel pipes to form voids in the stem and complete the connection between the piles and the stem.
  - The connection of the superstructure to the integral abutment is normally accommodated with a cast-in-place concrete closure pour.



# Abutments

## Alt. 2: Precast Integral or Semi Integral Abutment

- Abutment Details
  - Corrugated metal pipe voids- Placed over pile and filled with concrete
  - Detail developed by Iowa DOT
  - Reduces element weight
  - Has large capacity to transfer pile loads
  - Shear transfer via shear friction




## Abutments

### Alt. 2: Precast Integral or Semi Integral Abutment

#### Abutment Cap to Cap Connection


- Use Utah DOT Details
  - Concreted key
  - Use integral diaphragm to link caps together



# Abutments

## Alt. 2: Precast Integral or Semi Integral Abutment

### Completed Abutment




# Abutments

## Alt. 2: Precast Integral or Semi Integral Abutment

### Superstructure to Abutment Connection

- Use CIP Closure Pour
- Utah DOT Detail
- Allows for significant adjustability
- Provides connection between abutment stem elements



# Abutments


## Alt. 2: Precast Integral or Semi Integral Abutment



# Abutments


## Alt. 3: Geosynthetic Reinforced Soil (GRS) System

- This method involves combining the foundation, abutment and approach embankment into one composite material.



# Abutments

## Alt. 3: Geosynthetic Reinforced Soil (GRS) System




# Abutments

## Alt. 3: Geosynthetic Reinforced Soil (GRS) System




# Substructure: Abutments Alternatives


Alt. 1: Precast Cantilever Abutment



Alt. 2: Precast Integral or Semi-Integral Abutment



Alt. 3: Geosynthetic Reinforced Soil (GRS) System



Substructure elements:

# Foundations


Options compatible with ABC that will be evaluated:

- **Alternative 1:** Full Precast Footing
- **Alternative 2:** Partial precast Footing
- **Alternative 3:** Precast Pile Cap Footings



# Foundations

## Alt. 1: Full Precast Footing

- Ideal for footings small enough that can be transported and lifted as a single piece.



Shim and grout under footing  
through ports in footing



# Foundations


## Alt. 1: Full Precast Footing



# Foundations

## Alt. 2: Partial Precast Footing


- Ideal for larger footings
- Precast portion designed to support dead load of bridge
- Cast in place extension designed for other loads



Precast Portion

CIP Extension

Shim and grout under footing  
through ports in footing




# Foundations

## Alt. 2: Partial Precast Footing

### Footing to footing connection


- Use cast in place closure pour
- Cast closure pour during structure erection
- Design precast for structure Dead Load
- Design continuous footing for total loads



## Foundations



### Alt. 3: Precast Pile Cap Footings

- Pile Caps are made of precast concrete.
- Grouted pockets or corrugated steel pipe voids can be used to connect the piles to the cap.




# Foundations

## Alt. 3: Precast Pile Cap Footings




**PRECAST FOOTING ON DRILLED SHAFTS OR PIPE PILES**





**PRECAST FOOTING ON STEEL H-PILE**

# Substructure: Foundations Alternatives


## Alt. 1: Full Precast Footing



Shim and grout



## Alt. 2: Partial Precast Footing



## Alt. 3: Precast Pile Cap Footings

